TALUK BOARD OFFICE, HOSKOTE.

Dated 20th January 1927.

Notice is hereby given that sealed tenders will be received at the office of the President, District Board, Bangalore, up to 1 P.M., on 15th February 1927, for opening a fair weather road from 7/25 of Madras-Cannanur road to Toranahalli, Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1927.

2. The plans and detailed estimate and conditions may be seen at the Office of the President, District Board, Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the President, District Board. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed

3a. The terms should be definite. Representing merely less percentages will not be accepted.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for opening out a fair weather road from 7/25 of Madras-Cannanur road to Toranahalli Malur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of the same.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Office of the President, District Board, in due course. No enquiries regarding the acceptance or rejection of a tender will be made.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract for opening a fair weather road from 7/25 Madras-Cannanur road to Toranahalli, Malur Taluk :—

No.	Item of work	Unit	Quantity
1	Earthwork excavation side and cheeke drains ...	C.yd.	3220
	Forming approaches	,,	700
	Fixing of mile stones as per type design, complete	Each	2
	Do furlong stones do	,,	9
	Clearing jungle Furlong ..	..	10
2	Constructing 3' x 3' tunnel earthwork excavation	C.yd	23
	Burnt stone in mortar	C.ft	250
	Pointing with mortar	Sqr.	144
	Forming roadway and approaches ..	L. S.	Rs. 5
	Rough stone work	C.yds.	8
3	Constructing tunnel 4' x 5' earthwork excavation	,,	31
	Burnt stone in mortar ..	C.ft.	727
	Burnt stone slabs	S.ft.	225
	Pointing with mortar	Sqr.	292
	Forming roadway	L. S.	..
	Rough stone apron	C.yds.	15
4	Constructing causeways in 3 1 + 6/1 ..	..	..
	Earthwork excavation	C.yds.	28
	Rough stone work	,,	28
	Burnt stone slabs	S.ft.	72

B. SOMANNA,
President.